

Mike.Armani@constructem.com  
 JennyJames@constructem.com  
 (718) 554 3366



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENC E UNIT COST	REFERENCE TOTAL COST
<b>04 00 MASONRY</b>										
<b>BLOCK MASONRY</b>										
<b>TRASH ENCLOSURE</b>										
<b>8" CMU WALL</b>										
1	A-1.13	A-1.13		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C	392	10%	431	SF		\$ -
2	A-1.13	A-1.13		Bond Beam (2) #5 Continuous Bar	49	10%	54	LF		\$ -
<b>Scaffolding</b>										
3	A-1.13	A-1.13		Half height Scaffolding	49	10%	54	LF		\$ -
					<b>SUB TOTAL</b>					\$ -
<b>PATIO AREA</b>										
<b>8" CMU WALL</b>										
4	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 24" O.C	213	10%	234	SF	\$ -	\$ -
5	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	50	10%	55	LF	\$ -	\$ -
6	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area	50	10%	55	LF		\$ -
<b>8" CMU WALL</b>										
7	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 32" O.C	184	10%	202	SF	\$ -	\$ -
8	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	60	10%	66	LF	\$ -	\$ -
					<b>SUB TOTAL</b>					\$ -
<b>STONE CAP</b>										
<b>PATIO AREA</b>										
9	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area on 8" CMU Wall	50	10%	55	LF		\$ -
					<b>SUB TOTAL</b>					\$ -
<b>VEENER @ FIRE PIT</b>										
<b>BRICK VEENER @ FIRE PIT</b>										
10	A-1.14	A-1.14		Brick Veneer @ Fire Pit	213	10%	234	SF		\$ -
11	A-1.14	A-1.14		Pre Fab Top with Slate Tile (01 Each)	17	10%	18	SF		\$ -
					<b>SUB TOTAL</b>					\$ -

Mike.Armani@constructem.com  
 JennyJames@constructem.com  
 (718) 554 3366



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENC E UNIT COST	REFERENCE TOTAL COST
				<b>CRAFT VENEER MASONRY</b>						
				<b>PATIO AREA</b>						
12	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	426	10%	469	SF		\$ -
13	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	420	10%	462	SF	\$ -	\$ -
14	A-1.13	A-1.13		Scaffolding	420	10%	462	SF		\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>PORTE COCHERE</b>						
15	A-1.12	A-1.12		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	395	10%	435	SF		\$ -
16	A-1.12			Scaffolding	395	10%	435	SF	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>SOUTH ELEVATION</b>						
17	A-2.01	3/A5.01		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	226	10%	249	SF	\$ -	\$ -
18	A-1.12			Scaffolding	302	10%	332	SF	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>EAST ELEVATION</b>						
19	A-2.01	2/A-7.04		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	3,699	10%	4,069	SF		\$ -
20	A-1.12			Scaffolding	4,111	10%	4,523	SF	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -
				<b>NORTH ELEVATION</b>						
21	A-2.01			ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	651	10%	716	SF	\$ -	\$ -
22	A-1.12			Scaffolding	891	10%	980	SF	\$ -	\$ -
				<b>SUB TOTAL</b>						\$ -

Mike.Armani@constructem.com  
 JennyJames@constructem.com  
 (718) 554 3366



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENC E UNIT COST	REFERENCE TOTAL COST
<b>WEST ELEVATION</b>										
23	A-2.01	1/A-5.02, 3/A5.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	2,232	10%	2,455	SF	\$ -	\$ -
24	A-2.01			Scaffolding	4,038	10%	4,442	SF	\$ -	\$ -
<b>SUB TOTAL</b>										\$ -
<b>METAL COPPING</b>										
25	A-1.13	A-1.13		Metal Copping @ Trash Enclouser	49	10%	54	LF	\$ -	\$ -
26	A-1.11	A-1.11		Metal Copping @ Patio area	15	10%	17	LF	\$ -	\$ -
27	A-2.01			Metal Copping @ East Elevation	40	10%	44	LF	\$ -	\$ -
28	A-2.01			Metal Copping @ North Elevation	44	10%	48	LF	\$ -	\$ -
29	A-2.01			Metal Copping @ West Elevation	150	10%	165	LF	\$ -	\$ -