

info@constructem.com

(718) 719 2009

Rev 0



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	REFERENCE UNIT COST	REFERENCE TOTAL COST
04 00 MASONRY										
BLOCK MASONRY										
TRASH ENCLOSURE										
8" CMU WALL										
1	A-1.13	A-1.13		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C	392	10%	431	SF		\$ -
2	A-1.13	A-1.13		Bond Beam (2) #5 Continuous Bar	49	10%	54	LF		\$ -
Scaffolding										
3	A-1.13	A-1.13		Half height Scaffolding	49	10%	54	LF		\$ -
SUB TOTAL										\$ -
PATIO AREA										
8" CMU WALL										
4	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 24" O.C	213	10%	234	SF	\$ -	\$ -
5	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	50	10%	55	LF	\$ -	\$ -
6	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area	50	10%	55	LF		\$ -
8" CMU WALL										
7	A-1.11	A-1.11		8" Thick CMU wall Horizontal Reinforcement: Joint Reinforcement @ 16" O.C Vertical reinforcement: #5 @ 32" O.C	184	10%	202	SF	\$ -	\$ -
8	A-1.11	A-1.11		Bond Beam (2) #5 Continuous Bar	60	10%	66	LF	\$ -	\$ -
SUB TOTAL										\$ -
STONE CAP										
PATIO AREA										
9	A-1.11	A-1.11		1'-0" Wide Stone Cap @ Patio Area on 8" CMU Wall	50	10%	55	LF		\$ -
SUB TOTAL										\$ -
VENEER @ FIRE PIT										
BRICK VENEER @ FIRE PIT										
10	A-1.14	A-1.14		Brick Veneer @ Fire Pit	213	10%	234	SF		\$ -
11	A-1.14	A-1.14		Pre Fab Top with Slate Tile (01 Each)	17	10%	18	SF		\$ -
SUB TOTAL										\$ -

info@constructem.com

(718) 719 2009



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WAS TE	QTY. W/ WASTE	UNIT	REFERENCE UNIT COST	REFERENCE TOTAL COST
				CRAFT VENEER MASONRY						
				PATIO AREA						
12	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	426	10%	469	SF		\$ -
13	A-1.11	A-1.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick	420	10%	462	SF	\$ -	\$ -
14	A-1.13	A-1.13		Scaffolding	420	10%	462	SF		\$ -
				SUB TOTAL						\$ -
				PORTE COCHERE						
15	A-1.12	A-1.12		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	395	10%	435	SF		\$ -
16	A-1.12			Scaffolding	395	10%	435	SF	\$ -	\$ -
				SUB TOTAL						\$ -
				SOUTH ELEVATION						
17	A-2.01	3/A5.01		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath with Scratch Coat Over/ Weather Resistant Barrier	226	10%	249	SF	\$ -	\$ -
18	A-1.12			Scaffolding	302	10%	332	SF	\$ -	\$ -
				SUB TOTAL						\$ -
				EAST ELEVATION						
19	A-2.01	2/A-7.04		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	3,699	10%	4,069	SF		\$ -
20	A-1.12			Scaffolding	4,111	10%	4,523	SF	\$ -	\$ -
				SUB TOTAL						\$ -
				NORTH ELEVATION						
21	A-2.01			ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	651	10%	716	SF	\$ -	\$ -
22	A-1.12			Scaffolding	891	10%	980	SF	\$ -	\$ -
				SUB TOTAL						\$ -

Rev 0

info@constructem.com

(718) 719 2009



SR #	DWG. NO.	DETAIL NO.	CSI NO.	DESCRIPTION	QTY.	WASTE	QTY. W/ WASTE	UNIT	REFERENCE UNIT COST	REFERENCE TOTAL COST
				WEST ELEVATION						
23	A-2.01	1/A-5.02, 3/A5.11		ST-1 Craft Masonry Veneer Raincloud-Craft Warehouse Brick over/ Mortar Lath w/ Brown Coat O/Laticrete mortar O/ Wire Mesh & Brown Coat over/ 1" Rigid Insulation w/ Weather Resistant Barrier	2,232	10%	2,455	SF	\$ -	\$ -
24	A-2.01			Scaffolding	4,038	10%	4,442	SF	\$ -	\$ -
				SUB TOTAL						\$ -
				METAL COPPING						
25	A-1.13	A-1.13		Metal Copping @ Trash Encloser	49	10%	54	LF	\$ -	\$ -
26	A-1.11	A-1.11		Metal Copping @ Patio area	15	10%	17	LF	\$ -	\$ -
27	A-2.01			Metal Copping @ East Elevation	40	10%	44	LF	\$ -	\$ -
28	A-2.01			Metal Copping @ North Elevation	44	10%	48	LF	\$ -	\$ -
29	A-2.01			Metal Copping @ West Elevation	150	10%	165	LF	\$ -	\$ -